

OKANOGAN COUNTY COMMISSIONERS'

IN THE MATTER OF INITIATING COUNTY ROAD
PROJECT DESIGNATED AS CRP NO. 1882-02

Resolution No. 20 - 2015

WHEREAS, IT IS HEREBY RESOLVED THAT Road Chiliwist Road, OCR #1882, State Road Log No. 18820 Measure 1, from milepost 0.01 to milepost 0.86, Measure 2, at milepost 0.617, Measure 3, from milepost 0.59 to milepost 0.65, Measure 4, at milepost 0.815, Measure 5, at milepost 1.238 and Measure 6, at milepost 6.169 be improved as follows:

Measure 1 will line 3,450' of 6' wide by 9" deep and 504' of 16' wide by 9" deep ditch with quarry spalls and construct 5 quarry spall check dams. Measure 2 will install a 48" diameter corrugated metal overflow pipe 3' below the roadway surface and construct a 50' long by 10' wide riprap lined channel to the stream. Measure 3 will riprap armor 275' of ditch 16' wide by 1.5' deep and construct 6 riprap check dams. Measure 4 will install a 48" diameter corrugated metal overflow pipe 3' below the roadway surface and will riprap a 25' long by 15' wide channel to the stream. Measure 5 will install a 48" diameter corrugated metal overflow pipe 3' below the roadway surface and will riprap a 25' long by 15' wide channel to the stream. Measure 6 will install a 36" diameter corrugated metal overflow pipe 3' below the roadway surface and will riprap a 25' long by 15' wide channel to the stream.

This project is hereby declared to be a public necessity and the County Road Engineer is hereby ordered and authorized to report and proceed thereon as by law provided. (RCW 36.75.050, 36.80.030, 36.80.070)

NOW, THEREFORE, BE IT FURTHER RESOLVED that an appropriation from the officially adopted road fund budget and based on the County Engineer's estimate is hereby made in the amounts and for the purposes shown:

<u>PURPOSE</u>	<u>PROGRAM SOURCE</u>			<u>AMOUNT</u>
	<u>LOCAL FUNDS</u>	<u>STATE FUNDS</u>	<u>FEDERAL FUNDS</u>	<u>TOTAL</u>
Prelim Engr	\$ _____	\$ _____	\$ _____	\$ _____
R.O.W.	\$ _____	\$ _____	\$ _____	\$ _____
County Forces	\$ _____	\$ _____	\$ _____	\$ _____
Contract	\$ 31,798	\$ _____	\$ 95,392	\$ 127,190
Other	\$ _____	\$ _____	\$ _____	\$ _____
Const. Engr	\$ _____	\$ _____	\$ _____	\$ _____
TOTAL	\$ 31,798	\$ _____	\$ 95,392	\$ 127,190

(Check appropriate box)

This project is included in the officially adopted Annual Road Program as item #

- This project is hereby made a part of the officially adopted Annual Road Program in accordance with RCW 36.81.130

BE IT FURTHER RESOLVED: (Check appropriate box)

- The construction is to be accomplished by contract in accordance with RCW 36.81.130
- The construction is to be accomplished by county forces in accordance with RCW 36.77.060 and WAC 136-18

Dated at Okanogan, Washington this 17 day of February 2015.



ATTEST:

Laleña Johns
Laleña Johns, Clerk of the Board

**BOARD OF COUNTY COMMISSIONERS
OKANOGAN, WASHINGTON**

Jim DeTro
Jim DeTro, Chairman

Ray Campbell
Ray Campbell, Member

Sheilah Kennedy
Sheilah Kennedy, Member